

SCHEDULE OF PRICES

Chi941410B Project
 Contract No. 26-04
 Section 10, Township 94 North, Range 14 West, Chickasaw County, Iowa

Name of Bidder:

IMPACS Item No.	Eng. Item No.	Work or Material	Spec No.	Est. Quantity	Unit	Unit Price	Total
1	1	Site stripping & preparation	IA CS-001	1	LS		
	2	Crop Damages	IA CS-001	-	AC		
2	3	Pollution Control	IA-CS-005	1	LS		
3	4	Silt Fence	IA-CS-005	1,116	LF		
4	5	Structure Seeding	IA CS-006	1.1	AC		
5	6	Waterway Seeding	IA CS-006	0.1*	AC		
6	7	Buffer Seeding	IA CS-006	18.9	AC		
7	8	Mobilization and Demobilization	IA CS-008	1	LS		
8	9	Tile Investigation	IA CS-009	1	LS		
9	10	10' Long Sheet Pile	IA CS-013	460	SF		
10	11	7' Long Sheet Pile	IA CS-013	140	SF		
11	12	Excavation (Core Trench)	IA CS-021	1,985	CY		
12	13	Excavation (Borrow)	IA CS-021	8,175	CY		
13	14	Excavation (Sediment Forebay)	IA CS-021	230	CY		
14	15	Excavation (Tile Outlet Swale)	IA CS-021	25	CY		
15	16	Earthfill (Dam)	IA CS-023	6,270	CY		
16	17	Earthfill (Dam as Constructed)	IA CS-023	175	CY		
17	18	Earthfill (Dam Core)	IA CS-023	1,985	CY		
18	19	Earthfill (Diversion Dams)	IA CS-023	75	CY		
19	20	Earthfill (Submerged Berms)	IA CS-023	235	CY		
20	21	Drainfill, fine	IA CS-024	12	CY		
21	22	Topsoil Placement	IA CS-026	6,805	CY		
22	23	CMP Water Control Structure	IA CS-051	1	LS		
23	24	CMP Riser Inlet Structure	IA CS-051	1	EA		
24	25	CMP Pipe (15" DIA.)	IA CS-051	86	LF		
25	26	CMP Flared End Section w/ Bar Guard	IA CS-051	1	EA		
26	27	Riprap	IA CS-061	425	TON		
27	28	Concrete Grout	IA CS-062	8	CY		
29	29	Geotextile Fabric	IA CS-095	235	SY		

TOTAL BASE BID.....\$_____

Worksheet purposes only. Bids will only be accepted through the on-line Iowa Management of Procurement & Contracts System (IMPACS).

To register and learn about IMPACS, go to:

<https://solutions.sciquest.com/apps/Router/SupplierLogin?CustOrg=DASIowa>

***The waterway will appear in IMPACS as 1.0 acre and will be reduced manually in the bid tab.**

END OF DOCUMENT CC